

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 30 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Sargent of Mallonee-Mohoney has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Mallonee-Mahoney Inc.

Complete Address: Box 1257, Liberal, Kansas 67901

Lease Name: Berghaus Well No. 1

Location: C E/2 NE Sec. 10 Twp. 33 Rge. 29 (E) (W)

County Meade Total Depth 5738' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1389' circulated w/ cement. 4 1/2" to 5738' cemented.

Top perforations 5685' Plug bottom w/ 20 sacks cement

Top of cement 5122' Mud 5122' to 800'

Spot 35 sacks cement 800' to 700' Mud 700' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Edgar J. Eves
Conservation Division Agent