

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 15 1974
1-15-74
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Braley of W.R. Braley has this

date requested permission to plug the following described well:

Mr. Braley guarantees payment of the plugging fee.

Operator's full Name: William R. Braley

Complete Address: Box 768, Woodard, Oklahoma

Lease Name: Berghaus Well No. 1

Location: C W/2 NW Sec. 11 Twp. 33 Rge. 29 (E) (W)

County: Meade Total Depth 5750' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Braley was instructed to plug the well as follows:

8 5/7" to 1528' circulated w/ cement. 5 1/2" to 5749' cemented.


Top perforations 5677' Plug bottom w/ 20 sacks cement.

Top of cement 5600' Mud 5600' to 1000'

Spot 35 sacks cement 1000' to 900' Mud 900' to 45'

Plug, H₁lls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent