

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 15 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Dix of Skelly Oil Co. has this

date requested permission to plug the following described well:

Mr. Dix guarantees payment of the plugging fee.Operator's full Name: Skelly Oil CompanyComplete Address: 1860 Lincoln St., Denver, ColoradoLease Name: J.S. Williams Well No. 1Location: C NE NW Sec. 12 Twp. 33 Rge. 29 (E) (W)County Meade Total Depth 5779' Oil WellGas Well  Input Well  SWD Well  D & A  Lost Hole Mr. Dix was instructed to plug the well as follows:8 5/8" circulated w/ cement to 1394' 5 1/2" to 5779' cemented.Top perforations 5610' Plug bottom w/ 20 sacks cement.Top of cement 5375' Mud 5375' to 775'Rock bridge & 35 sacks cement 775' to 650' Mud 650' to 50'Rock bridge & 15 sacks cement 50' to 0' Company Pump

Very truly yours,

*Edgar J. Ford*  
Conservation Division Agent