

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

JAN 28 1964

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Saddie of Great Bend Pipe & Supply Co. Inc.

date requested permission to plug the following described well:

Mr. Saddie guarantees payment of the plugging fee.

Operator's full Name: Great Bend Pipe & Supply Co. Inc.

Complete Address: Drawer B Great Bend, Kansas

Lease Name: Borchers Well No. 1

Location: C SW/4 Sec. 21 Twp. 33 Rge. (E) (W) 28

County Meade Total Depth 6165' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Saddie was instructed to plug the well as follows:

8 5/8"-1415' Circulated w/cement, 5 1/2"-6041' Cemented.

Plug back w/cement 6165' to 5719' Perforations-5710' to 5700'

Plug bottom back w/5 Sax.cement 5719' to 5675' Mid 5675' to 700'

35 Sax.cement 700' to 600' Mid 600' to 50'

Rock bridge 50' to 40' 15 Sax.cement 40' to 0

Very truly yours,

*[Signature]*  
 Conservation Division Agent