

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

JAN 12 1972
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Davis of Kathol has this

date requested permission to plug the following described well:

Mr. Davis guarantees payment of the plugging fee.

Operator's full Name: Kathol Petroleum

Complete Address: 900 Sutton Place, Wichita, Kansas

Lease Name: Classen Well No. 1

Location: C SW NE Sec. 23 Twp. 33 Rge. 28 ~~(E)~~ (W)

County: Meade Total Depth 6000' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Davis was instructed to plug the well as follows:

8 5/8" to 1550' circulated w/ cement. 5 1/2" to 6000' cemented.


Top perforations 5101' Plug bottom w/ 25 sacks cement.

Top of cement. 4900' Mud 4900' to 1000'

Spot 35 sacks cement 1000' to 900' Mud 900' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent