

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

SEP 11 1973

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Trigg has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Trigg Exploration Company

Complete Address: 410 Woolworth Bldg., Boulder, Colorado

Lease Name: Hisson Well No. 1-31

Location: NW NW Sec. 31 Twp. 33 Rge. 28 XY (E) (W)

County: Meade Total Depth 3297' Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Sargent was instructed to plug the well as follows:

9 5/8" to 1539' circulated w/ cement. 4 1/2" to 3297' cemented.

Top perforations 3066' Plug bottom w/ 20 sacks cement.

Top of cement 2900' Mud 2900' to 900'

Spot 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

*Edgar J. Green*  
Conservation Division Agent