



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

AUG 23 1971
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Barker of Anadarko has this

date requested permission to plug the following described well:

Mr. Barker guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Company

Complete Address: Box 351, Liberal, Kansas

Lease Name: Harris Well No. 1

Location: C NW SW Sec. 5 Twp. 33 Rge. 28 (E)(W)

County: Meade Total Depth 5775' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Barker was instructed to plug the well as follows:

8 5/8" to 1531' circulated w/ cement. 4 1/2" to 5774' cemented.

Top perforations 5575' Plug bottom w/ 25 sacks cement.

Top of cement 5100' Mud 5100' to 900'

Spot 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent