

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

DEC 9 1966

Dear Sir:

CONSERVATION DIVISION
Wichita, Kansas

Mr. Boyd of Shamrock Oil & Gas has this

date requested permission to plug the following described well:

Mr. Boyd guarantees payment of the plugging fee.

Operator's full Name: Shamrock Oil & Gas Corp.

Complete Address: Box 631, Amarillo, Texas

Lease Name: Joe S. Fletcher Well No. 3

Location: 660' FNL ^{CENE} 660' FEL Sec. 7 Twp. 33 Rge. 28 ~~(E)~~ (W)

County Meade Total Depth 5768' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Boyd was instructed to plug the well as follows:

9 5/8" to 1551' circulated w/ cement, 4 1/2" to 5130' cemented.

Top Perforations 5082' Plug bottom w/ 20 sacks cement

Top of cement 4620' Mud 4620' to 1607'

Spotted 40 sacks cement 1607' to 1507' Mud 1507' to 30'

Plug, Fulls & 10 sacks cement 30' to 0'

Very truly yours,

Conservation Division Agent