

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 22 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Unruh of Abercrombie has this

date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: A.L. Abercrombie

Complete Address: 801 Union Center, Wichita, Kansas

Lease Name: Wiens Well No. 1

Location: C NW Sec. 11 Twp. 33 Rge. 28 XX (E) (W)

County: Meade Total Depth 5804' Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

8 5/8" to 1204' circulated w/ cement. 4 1/2" to 5801' cemented.

Top perforations 5711' Plug bottom w/ Bridge Plug at 5682'

hole in pipe at 3745' Spot sand & 3 sacks cement to 3650'

Mud 3650' to 600' Spot 35 sacks cement 600' to 500'

Mud 500' to 45' Plug, Hylls & 10 sacks cement 45' to 0'.

Very truly yours,

Edgar J. Green
Conservation Division Agent