

State of Kansas

FORM CP-2



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

### State Corporation Commission

#### CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

20 October 1981

#### VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Bob Sargant of Sargant's casing pulling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Diamond Shamrock Oil & Gas Co.

Complete Address: Box 631 Amarillo Texas 79133

Lease Name: J. J. Reiner Well No. 2

Location: 1650' from SL-990' from East Line Sec. 19 Twp. 33S Rge. 28W (E) (W)

County: Meade Total Depth: 5812'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated The production pipe was run & well tested but not produced

Mr. Sargant was instructed to plug the well as follows:

There is 1734' of 8 5/8" surface casing cement circulated. There was 5283' of 5 1/2" production pipe cemented to 4000'. Top of perforations were 5117' to 5130'. There is a cast iron plug at 5100' with 20' of cement on top of it. 1st plug with hole full of mud at 1700' with 50 lbs of cement pumped to bottom. 2nd plug on solid bridge at 40' to 0' with 10 lbs of cement. There was 3315' of production pipe recovered. Plugging accomplished by Sargant's casing pulling. Mr. Troy Cody, field production manager was advised about recording the water well with the Corporation. The water well is just southwest of #2 well. We didn't plug it this day.

Paul Luthri  
Conservation Division Agent

OCT 22 1981  
10-22-1981  
RECEIVED  
STATE CORPORATION COMMISSION  
Wichita, Kansas