

10-1-879-30070-0000

To: 1 030865
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Completion date 12/16/65

C W/2 SE, SEC. 1, T 33 S, R 29 W/X

1320 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5062

Lease Name Bessmer Well # 1

Operator: George R. Shaw (Was Edwin Bradley)

County Meade 184.05

Name & Address 1001 Union Center

Well Total Depth 5663 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1412

Abandoned Oil Well X Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 4 p.m. Day: 1 Month: 10 Year: 19 87

Plugging proposal received from Deacon Pulley

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 4 1/2" at 5641' PBSD 5573' Perfs at 5564-68'

1st plug sand back to 5510' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 3 sx gel and 150 sx econolite cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5 p.m. Day: 1 Month: 10 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 5500' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 3 sx gel, and 150 sx Halliburton Lite cement.

Maximum pressure 150 psi and shut in 50 psi.

Remarks: Used Halliburton Lite cement by Halliburton. Recovered 2500' of 4" casing. (If additional description is necessary, use BACK of this form.)

INVOICED
I (did not) observe this plugging.

DATE 10-7-87

WV. NO. 18418

Signed Steve Durrant CONSERVATION DIVISION (TECHNICIAN) WICHITA, KANSAS

RECEIVED
OCT 5 1987