

To: 1 061039
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-119-20,411 - 0000

SE SE SW, SEC. 19, T 33 S, R 28 W/E

330 feet from S section line

3064 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9123

Lease Name Harvey Feldman Well # 2

Operator: Maxus Exploration Company

County Meade 187.98

Name & Address P.O. Box 400

Well Total Depth 5784 feet

Address Amarillo, TX 79188

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1670

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pullers License Number 6547

Address 620 South Lincoln, Liberal, KS 67901

Company to plug at: Hour: 10 a.m. Day: 4 Month: 12 Year: 19 87

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pullers (phone) 316-624-7455

were: 5 1/2" at 5789' PBD 5789' Perfs at 5666-78' Elevation 2440'

1st plug pump 25 sx cement to bottom, 2nd plug pump 50 sx cement at 1620-1720',

3rd plug pump 40 sx cement at 750-655', 4th plug pump 10 sx cement at 33-3'.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 2 p.m. Day: 5 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 25 sx cement,

2nd plug pumped 50 sx cement at 1620',

3rd plug pumped 40 sx cement at 750',

4th plug pumped 10 sx cement at 33'.

RECEIVED
STATE CORPORATION COMMISSION

DEC 8 1987
12-8-87

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 2621' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

DATE 12-8-87

Signed Paul A. Luttich (TECHNICIAN)

INV. NO. 19228