

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAY 26 1972

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Diamond Shamrock Corporation

Complete Address Box 631, Amarillo, Texas

Lease Name R.C. Carter "A" Well No. 2

Location C NW NW Sec. 25 Twp. 33 Rge. 31 (E) (W)

County Seward Total Depth 6068'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated None

Plugging Contractor Sargents Casing Pulling Co

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 2:00PM Day 24 Month 5 Year 1972

The above well was plugged as follows:

9 5/8" to 1511' circulated w/ cement. 5 1/2" to 6066' cemented.

Top perforations 4904' Bottom plugged w/ sand 4977' to 3400'

Mud 3400' to 900' Spotted 55 sacks cement 900' to 750'

Mud 750' to 45' Plug, Hulls & 15 sacks cement 45' to 0'.

Company Pump Pulled 2621' of 5 1/2" casing.

Plug back T. D. was 4977'.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edmund J. Eves  
Well Plugging Supervisor

DATE 5/26/72

INV. NO. 5757-W