

15-175-10069-0000 R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
FEB 26 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name A.L. Abercrombie Inc.

Complete Address 801 Union Center Bldg., Wichita, Kansas

Lease Name Fredrick Well No. 6

Location SE SW Sec. 26 Twp. 33 Rge. 31 (E) (W)

County Seward Total Depth 5925'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Sargents Casing Pulling

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 4:00PM Day 19 Month 2 Year 1974

The above well was plugged as follows:

8 5/8" to 1242' circulated w/ cement. 5 1/2" to 5924' cemented.

Top perforations 5836' Plug bottom w/ 20 sacks cement.

Top of cement 5550' Mud 5550' to 800'

Spotted 35 sacks cement 800' to 700' Mud 700' to 45'

Plug, Halls & 15 sacks cement 45' to 0'. Company Pump

Pulled 2600' of 5 1/2" casing

INVOICED
I hereby certify that the above well was plugged as herein stated.

DATE 2/27/74

INV. NO. 8641-W

Signed: [Signature]
Well Plugging Supervisor