

*al*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
APR 15 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Skelly Oil Company

Complete Address: 1860 Lincoln St., Denver, Colorado 80203

Lease Name J.S. Williams Well No. 1

Location C NE NW Sec. 12 Twp. 33 Rge. 29 (E) (W)

County Meade Total Depth ~~5669'~~ 5779'

Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A X

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling

Address: Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 4:00PM Day 11 Month 4 Year 1968

The Above well was plugged as follows:

8 5/8" to 1394' circulated w/ cement. 5 1/2" to 5779' cemented.

Top perforations 5610' Plug bottom w/ 20 sacks cement.

Top of cement 5375' Mud 5375' to 775'

Rock bridge & 35 sacks cement 775' to 650' Mud 650' to 50'

Rock bridge & 15 sacks cement 50' to 0'. Company Pump

Pulled 4758' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/15/68  
INV. NO. 4588-11

Signed: *Edward J. Gales*  
Well Plugging Supervisor