

SEP 21 1981

STATE CORPORATION COMMISSION

CONSERVATION DIVISION
Wichita, Kansas

CONSERVATION DIVISION AGENT REPORT

Amended report

API Number 15- H9-20522-0000

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name Southwest Gas + Storage

Complete Address PO Box 627, Meade, Kansas

Lease Name Mc Naghten Well No. 3-4

Location 1200 FSL - 1600 FNL Sec. 4 Twp. 33 Rge. 28 (East) (West)

County Meade Total Depth 1424

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated Last Hole

Plugging Contractor Patrick Oil Service

Address Liberal Kansas License No. _____

Operation Completed: Hour: 4:00 PM Day: 16 Month: Sept Year: 1981

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

There was 65' of 20" conductor set.
On or about 19th Aug at 4:00 PM Mr.
Frank Crowl of Southwest Gas + Storage
called to inform me that a large drilling
rig had settled approximately 4' on Aug
3, 1981. At 3:00 PM. They took 2 large cranes
and 5 Caterpillar tractors to remove the
rig. They had to set 12 1/2 bit, 2-8" collars
#4-6 1/2" collars + 35 1/2" drill stem on bottom

I hereby certify that the above well was plugged as herein stated.

NOTICED
DATE 10-20-81
INV. NO. 8234-W

Signed: _____
Conservation Division Agent

To help hold up rig. All they could recover was 160' of 4 1/2" drill stem all other tools were left in the hole. On Sept 15, 1981 at 8:00 AM we took 2 7/8 tubing and hook it to Patrick well service rig. Halliburton started circulating mud & we washed down to 210'. The tubing would go no further. At 8:00 AM on the 16th Sept 81. They had power swivel from beam tool of lateral start to drill with a 3 7/8 bit. We got the hole to 401' at 3:00 PM on the 16th Sept 81. Halliburton then pumped a 1000 lbs of cement into the hole. Completing the cementing at 4:00 PM on the 16th of Sept. There was good return on cement.

Mr. Don Ubel of Health & Environment of Dodge City Ks was contacted on numerous occasions & he was very happy that we got the well cemented from 401' to top.

There was a free flowing water well 117' deep that set 100' Northwest of location. on Sept 16, 1981. at 5:00 PM it was flowing very fresh water.

I contacted Mr. Dennis Carlie at Meade at 10:00 PM on the 18th Sept and all cement is standing at top of hole.

Clarence Thomas

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

200 Colorado Derby Bldg.
Wichita, KS 67202

API Number 15- 149-20,522-0000

Operator's Full Name Southwest Gas & Storage Co.

Complete Address Nye Rt; Post Box 62A, Meade Kans

Lease Name Mc Naghten Well No. 3-4

Location 1200' S - 1600' W NE 1/4 Sec. 4 Twp. 33 Rge. 28 (East) (West)

County Meade Total Depth 1424

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated Lost Hole

Plugging Contractor Hal Luberton

Address Liberal Kans License No. _____

Operation Completed: Hour: 4:00 PM Day: 16 Month: Sept Year: 1981

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1981
CONSERVATION DIVISION
Wichita Kansas

There was 65' of 20' condutor.
Sage Drilling was drilling well & on the
3rd of August at 3:00 PM the ground gave
up & the rig settled 4'. Moved rig off.
They hired a work over rig to go in
& was it down. At 2:10 we could not go
any further called in a small rig & drilled
to 400'. Pumped a 1000 lbs of cement into
hole. We got good return on our cement.

I hereby certify that the above well was plugged as herein stated.

Accomplished by
Hal Luberton

Signed: Clarence Thomas
Conservation Division Agent

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

200 Colorado Derby Bldg.
Wichita, KS 67202

API Number 15- 119-20,522-0000

Operator's Full Name Southwest Gas & Storage Co.

Complete Address Nye Rt, Post Box 624, Meade Kans

Lease Name Mc Naghten Well No. 3-4

Location 1200' 5-1600' W NE 1/4 Sec. 4 Twp. 33 Rge. 28 (East) (West)

County Meade Total Depth 1424

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated Lost Hole

Plugging Contractor Halliburton

Address Liberal Kans License No. _____

Operation Completed: Hour: 4:00 PM Day: 16 Month: Sept

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1981
CONSERVATION DIVISION
Wichita Kansas

There was 65' of 20' conductor.
Sage Drilling was drilling well & on the
3rd of August at 3:00 PM the ground gave
way & the rig settled 4'. Moved rig off.
They hired a work over rig to go in
& was it down. At 210' we could not go
any further called in a small rig & drilled
to 400'. Pumped a 1000 lbs of cement into
hole. We got good return on our cement.

I hereby certify that the above well was plugged as herein stated.

Accomplished by
Halliburton

Signed: Clarence Thomas
Conservation Division Agent