

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 23 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Anadarko Production Company

Complete Address Box 351, Liberal, Kansas

Lease Name Harris Well No. 1

Location C NW SW Sec. 5 Twp. 33 Rge. 28 (E) (W)

County Meade Total Depth 5775'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated None

Plugging Contractor Sargent Casing Pulling Co.

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 4:00PM Day 17 Month 8 Year 1971

The above well was plugged as follows:

8 5/8" to 1531' circulated w/ cement. 4 1/2" to 5774' cemented.

Top perforations 5575' Plug bottom w/ 25 sacks cement

Top of cement 5100' Mud 5100' to 900'

Spotted 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Halls & 15 sacks cement 45' to 0'. Company Pump

Pulled 2708' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 8/30/71

INV. NO. 4217-W