

KANSAS

FORM CP-3  
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-119-20560-0000

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Texas oil & Gas Corp

Complete Address 200 West Douglas Suite 300 Wichita Kansas 67202

Lease Name Ediger Well No. C1

Location 2310' FSL - 2310' EL CNWSE Sec. 11 Twp. 33 Rge 28W (East) (West)

County Meade Total Depth 5819'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor H-30 Drilling Co. Inc.

Address 251 N. Water Wichita Kansas 67202 License No. \_\_\_\_\_

Operation Completed: Hour: 10:15 AM Day: 8 Month March Year: 19 82

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

1st plug at 5819' with 150 bbl of 50/50 paracement  
The rest of hole cemented with class H cement pumped through  
drill pipe with hole full of heavy mud. 2nd plug at 1630' with  
60 bbl of cement. 3rd plug at 860' with 35 bbl of cement 4th  
plug on solid bridge at 40' to 50' with 10 bbl of cement. Then  
circulated 10 bbl of cement in rat hole & 5 bbl of cement  
in mouse hole. The cementing was accomplished by  
Halliburton Co out of Liberal Kansas.

Amount of Surface Casing: 1621' of 8 3/8" cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul Lutter  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED  
STATE CORPORATION COMMISSION

Signed: \_\_\_\_\_  
Conservation Division Agent  
Wichita, Kansas

MAR - 9 1982

INVOICED

DATE 3-10-82

INV. NO. 9599W