

15-119-00096-0000

R  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

DEC 23 1959

CONSERVATION DIVISION  
Wichita, Kansas

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Woods  
Location: N E SW SW Sec. 16 Twp. 33 Rge. 28 (E) (W)   
Name of Field: \_\_\_\_\_ Total Depth: 5840

I have this date completed supervision of plugging of:

Lease Name: Borchers Well No. 1  
Operator's Full Name: The Shumard Oil & Gas Corp  
Complete Address: Box 631, Jewell, Texas  
Plugging Contractor: Forbes Coiling Pulling Co.  
Address: 10 East Bond Road License No. 49  
Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 11:30 am Day 13 Month Dec Year 1959

The above well was plugged as follows:

1536' of 9 7/8" surface casing 4 1/2" set at 3830'. Top  
perf. 5158'. Hole was mudded to 5150 and 4 sacks  
of cement dumped, with large lumps. Hole filled to 600'  
with heavy mud. Rock bulge set from 600 to 590'  
25 sack cement dumped on bulge. Hole mudded to  
5575'. Rock bulge from 75 to 65. 10 sack cement dumped.  
Mud to 25'. Rock bulge set at 25 and 5 sack cement  
to base of well.

Signed: [Signature]  
Conservation Division Agent

Reviewed: J. Lewis Brock  
Field Supervisor

Remarks:

INVOICED  
DATE 1/13/60  
INV. NO. 508-w