

KANSAS

FORM CP-3 RECEIVED
Rev. 5-15-78 STATE CORPORATION COMMISSION

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

OCT 22 1981
10-22-81
CONSERVATION DIVISION
Wichita, Kansas

API Number 15-119-20,422

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name Diamond Shamrock Oil & Gas Co.

Complete Address Box 631 Amarillo Texas 79133

Lease Name J. J. Reinen Well No. #1

Location 1650' FSL - 990' FEL Sec. 19 Twp. 33S Rge. 28W (East) (West)

County Meade Total Depth 5812'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated The production pipe was run & tested but not produced

Plugging Contractor Sargent's Casing Pulling Service

Address 620 S. Lincoln, Box 506 Liberal Kans License No. 511

Operation Completed: Hour: 2:00 PM Day: 21 Month: October Year: 19 81

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

There is 1734' of 8 7/8" surface casing cement circulated. There was 5283' of 5 1/2" production pipe cemented to 4000'. Top of perforations were 5117' to 5130'. There is a cast iron at 5100'. 1st plug at 1700' with hole full of mud they pumped 50 bbls. of cement to 1700'. 2nd plug on solid bridge with 1 bbl. shells & 10 bbls of cement at 40' to 0'. There was 20' of cement on top of cast iron plug. Plugging accomplished by Sargent's casing pulling co. There was 3315' of production pipe recovered. Diamond Shamrock's production fieldman Mr. Troy Cody was advised about recording the water well that is just south west of #2 well. We didn't plug it this day.

I hereby certify that the above well was plugged as herein stated.

DATE 11-19-81

Signed: Paul Luthi
Conservation Division Agent

INV. NO. 8329-W