

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # _____ EXPIRATION DATE _____

OPERATOR Anadarko Production Company API NO. 15-189-20,605 -00-00

ADDRESS Box 351 COUNTY Stevens

Liberal, Kansas 67901 FIELD Panoma Council Grove

** CONTACT PERSON Paul Gatlin PROD. FORMATION Council Grove

PHONE 316-624-6253

PURCHASER Panhandle Eastern Pipe Line Company LEASE Gregory "C"

ADDRESS Box 389 WELL NO. 1

Liberal, Kansas 67901 WELL LOCATION _____

DRILLING Gabbert-Jones, Inc. 1250 Ft. from North Line and

CONTRACTOR 830 Sutton Place 1250 Ft. from East Line of

ADDRESS Wichita, Kansas 67202 the NE (Qtr.) SEC 29 TWP 33S RGE 38W.

PLUGGING _____ WELL PLAT _____ (Office Use Only)

CONTRACTOR _____

ADDRESS _____

TOTAL DEPTH 3040 PBD 3011

SPUD DATE 6/1/82 DATE COMPLETED 6/18/82

ELEV: GR 3190 DF 3192 KB 3193

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE _____

		29	

KCC
KGS
SWD/REP _____
PLG. _____

Amount of surface pipe set and cemented 600 DV Tool Used? No

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other _____

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

Paul Campbell, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

Paul Campbell
(Name)

SUBSCRIBED AND SWORN TO BEFORE ME this 25th day of June, 19 82.

MY COMMISSION EXPIRES:

NOTARY PUBLIC
ELIZABETH J. HOOPER
Seward County, Kansas
My Appt. Expires 7-26-83

Elizabeth J. Hooper
(NOTARY PUBLIC)

RECEIVED
STATE CORPORATION COMMISSION
JUN 29 1982

** The person who can be reached by phone regarding any questions concerning this information.

CONSERVATION DIVISION
Wichita, Kansas

FILL IN WELL LOG AS REQUIRED:

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
			NAME	DEPTH
Surface Clay-Redbed	0'	490'		
Clay-Redbed	490'	620'		
Redbed	620'	1160'		
Sand	1160'	1360'		
Shale	1360'	1800'		
Shale-Shells	1800'	2020'		
Shale	2020'	2505'		
Shale-Lime	2505'	2990'		
Lime-Shale	2990'	3040'		
TD	3040'			

Report of all strings set—surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4	8-5/8	20#	600	Common	600	3% CaCl
Production	7-7/8	4-1/2	10.5#	3034	Litewate ss Pozmix	500 150	.5% CFR ₂ .5% CFR ₂

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	.46	2882-88'
			2	.46	2847-2988' OA

TUBING RECORD

Size	Setting depth	Packer set at
2-3/8	2829	None

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidize w/400 gal 15% HCl + 15 BS	2882-88'
Acidize w/4600 gal 15% HCl + 213 BS	2847-2988' OA
Frac w/190,000 gal wtr, 280,000# river sand	2847-2988' OA
Date of first production SI for pipeline	Producing method (flowing, pumping, gas lift, etc.) Flowing
Gravity	
RATE OF PRODUCTION PER 24 HOURS	Oil bbls. 1020 MCFD Water % Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold) To be sold	Perforations Council Grove 2847-2988' OA