

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH

Pratt County. Sec. 14 Twp. 28S Rge. 12W (E) (W)
NW¼SW¼ or footage from lines E/2-SB/4-SB/4 W+2 SW/4 1/2 SW¼

Location as "NE/CNW/SW" or footage from lines E 7-8-74-10-74 W 1-2 SW 1-4 E 3 SW 1-4
 Lease Owner Raymond Oil Co., Inc.

Lease Owner Raymond Oil Co., Inc.
Chitwood 078

Lease Name Chitwood U#0 Well No. _____
 or Wichita, Kansas 67202

Office Address _____ Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19__

Application for plugging filed _____ 19____

Application for plugging approved _____ 19____

Plugging commenced 10/15/69 10/24/69 1969

Plugging completed 10/24/69 1969

Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was com-

menced? yes

Name of Conservation Agent who supervised plugging of this well Warren

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4296 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, pushed plug to 4250', ran sand and 5 sacks of cement.
Loaded hole with water, checked hole, shot pipe at 3208', spotted oil
and pushed plug to 3150', 3114', 2885', spotted 30 barrels of oil
to 2850', checked hole, had plug at 1731', pumped plug down, shot pipe at 2732', worked
worked pipe, shot pipe at 2567', 2449', 2321', 2203', 2110', 2005', pulled 65
joints. Bailed hole to 250', set 10' rock bridge and ran 25 sacks of cement.
Mudded to 40', 10' rock bridge and ran 10 sacks of cement.

~~PLUGGING COMPLETE.~~

RECEIVED
STATE CORPORATION COMMISSION
OCT 30 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.

Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner of

NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wm. Knecht
CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN to before me this 27th day of October, 1969

My commission expires.

2/15/71

Notary Public.

INDIVIDUAL WELL RECORD

PAGE NO. 1

GENERAL INFORMATION

FORM NO. 176 - PAGE 1

Operator Monsanto Chemical Company
(Lion Oil Company Division) Lease Chitwood Unit Well No. 0-8
Lease Ownership Chitwood Unit

Lease No. _____ Sec. 14 Twp. 28S Rge. 12W County Pratt State Kansas
Location W/2 SW 14 E/2 SW SW? Field or Pool Chitwood

Elevation D. F. 1860' Elevation Rot. Bushing

Contractor Ruso Drilling Company

Drilling Began 10-26-45 Drilling Ended 1-31-46

Maximum Deviation of Hole 5 Degree

Rotary Tool Footage 4419' Cable Tool Footage 12'

Drillers T. D. 4419 Schlumberger T. D.

Total Depth Corrections.

Float Collar' Size 5 1/2" Set at _____ Guide Shoe Set at 4439' (From Rotary Bushing)

Total Depth Drilled out to 4439' - PBTD = 4419'. (From Rotary Bushing)

Remarks

CASING AND LINER RECORD

[illegible]