

15-151-21263-DD-02

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pratt SEC. 21 TWP. 28S RGE. 12 ~~W~~
Location as in quarters or footage from lines:
990' FSL 1650' FWL

Locate Well
correctly on above
Section Platt.

Lease Owner Bankoff Oil Company
Lease Name Banbury Well No. 1
Office Address 6202 S. Lewis, Suite 176, Box 3446, Tulsa OK 74101
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed 5-08-83
Application for plugging filed yes
Plugging commenced 5-09-83
Plugging completed 5-09-83
Reason for abandonment of well or producing formation Dry Hole

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Richard Lacy
Producing formation _____ Depth to top _____ bottom _____ T.D. 4,510'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				14-3/4"	340'	

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Mud to 660' hull plug, 40 sacks cement. Mud to 360' hull plug, 40 sacks cement.
Mud to 40' hull plug, 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glacier Drilling Company, Inc.

STATE OF OKLAHOMA COUNTY OF TULSA, ss.
Julius M. Bankoff (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Julius M. Bankoff
Bdx 3446, Tulsa, OK 74101
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of May, 19 83

Verna Doty
Verna Doty Notary Public.
STATE CORPORATION COMMISSION

My Commission expires: Feb 5, 1985

MAY 16 1983

CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

S. 21 T. 28 R. 12 ^E/_W


API No. 15 - 151 - 21,263
County Number

Loc. NW SE SW

County Pratt

Operator Bankoff Oil Company		
Address 6202 S. Lewis, Suite 176 P. O. Box 3446 - Tulsa, OK 74101		
Well No. 1	Lease Name Banbury	
Footage Location 990 feet from (N) S. line 1650 feet from (E) W. line		
Principal Contractor Glacier Drilling Co., Inc.		Geologist Frank Mize
Spud Date 4/26/83	Total Depth 4510'	P.B.T.D. 4600'
Date Completed 5/8/83		Oil Purchaser

640 Acres
N



Locate well correctly

Elev.: Gr. 1881'

DF KB 1886

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
SURFACE	14 3/4"	10 3/4"	40#	340'	50-50 POS	300	3% CC 2% GEL
PRODUCTION							

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

Formation	Top	Btm.	Formation	Top	Btm.	Formation	Top	Btm.
Topsoil	0	12						
Sandy Shale	12	110						
Shale & Lime	110	155						
Sand	155	240						
Shale	240	1693						
Shale W/Lm Stk	1693	2111						
Fort Riley	2111	2259						
Wre Ford	2259	2461						
Cottonwood	2461	2568						
Red Eagle	2568	2690						
Indian Cave	2690	2733						
Wabaunsee	2733	2930						
Tarkio	2930	3021						
Howard	3021	3190						
Topeka	3190	3559						
Heebner	3559	3576						
Toronto	3576	3588						
Douglass	3588	3744						
Brow Lime	3744	3760						
Lansing	3760	4196						
Mississippi	4196	4375						
Viola	4375	4462						
Simpson	4462	4510						