

WELL PLUGGING RECORD


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

PRATT

County, Sec. 20 Twp. 28S Rge. 12W (E) (W)

Location as "NE/CNW/SW" or footage from lines. SW SW NE  
Lease Owner. CONTINENTAL OIL COMPANY  
Lease Name. MARTIN Well No. 1  
Office Address. BOX 2197, HOUSTON, TEXAS  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed. DECEMBER 8, 19.62  
Application for plugging filed. DECEMBER 8, 19.62  
Application for plugging approved. DECEMBER 8, 19.62  
Plugging commenced. DECEMBER 9, 19.62  
Plugging completed. DECEMBER 9, at 7 a.m. 19.62  
Reason for abandonment of well or producing formation. DRY HOLE

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production. 19.\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well. HERMAN E. JUSTUS, NICKERSON, KANSAS  
Producing formation. \_\_\_\_\_ Depth to top. \_\_\_\_\_ Bottom. \_\_\_\_\_ Total Depth of Well. 4546 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SURF. CLAY, SAND, GRAVEL						
RED BED, SHALE & SHELLS	SURFACE CSG.	-0-	913' KB	10-3/4"	913'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

PLUGGED: Filled hole with heavy mud 4546' up to 200'. Set bridge using Halliburton plug, 1/4 sk. mills, 25 sx. cement through drill pipe by Halliburton. Filled hole with heavy mud up to 40', 1/4 sk. mills, Halliburton plug, 15 sx. cement through drill pipe by Halliburton to cellar zero.

Job completed 7 a.m. 12-9-62.

DEC 11 1962

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor. SIERRA PETROLEUM CO., INC.  
Address. 208 PETROLEUM BUILDING, WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
C. T. HONAKER, DRILLING SUPERINTENDENT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. T. Honaker C. T. HONAKER, DRIG. SUPT.  
BOX 232, RUSSELL, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 10TH day of DECEMBER, 19 62

My commission expires 10-17-63

*Jerry Dyer*  
Notary Public.



CONTINENTAL OIL COMPANY - Operator

SIERRA PETROLEUM CO., INC - Contractor

MARTIN #1  
SW SW NE  
Sec. 20-28S-12W  
Pratt County, Kansas

T. D.: 4546'  
Elev.: 1882' D.F.

Commenced: 11-21-62  
Completed: 12-8-62

Casing:

10-3/4" Set at 913' K.B.

Cement:

with 400 sx. cement

FORMATION

DEPTH

Surface Clay & Sand	40
Sand & Gravel	250
Red Bed	675
Shale & Shells	918
Shale	1385
Salt & Shale	1550
Shale & Shells	1750
Lime & Shale	3170
Chalky Lime & Shale	3345
Lime & Shale	3400
Lime	3635
Lime & Shale	3812
Lime	4440
Viola	4509
Viola & Simpson	4523
Simpson	4546

STATE OF KANSAS

DEC 11 1962

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
                          ) ss:  
COUNTY OF RUSSELL )

I hereby certify that the above information is true and correct to the best of my knowledge.

C.T. Honaker  
Drilling Superintendent

Subscribed and sworn to before me this 10th day of December, 1962.

Lesay Giegl  
Notary Public

My commission expires: 10-17-63