


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above Section Plot

Pratt County, Sec. 22 Twp. 28s Rge. 14w E/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{4}$ " or footage from lines _____
NE NE NE
Lease Owner Raymond Oil Co.
Lease Name Chitwood Well No. Mo
Office Address One Main Place Suite 900 Wichita Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____
Input _____
Date Well completed 8-27-53 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 2-16-80 19____
Plugging completed ~~###/###/###~~ 1-5-81 19____
Reason for abandonment of well or producing formation _____
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Thompson
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 441.5
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	393'	none
				###/###/###	###	
				5 1/2	445.	265.3

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded hole to 2700' set five sks. cement with bailer
Recovered 2653' of 5 1/2" casing
Pressured up on surface pipe Pipe had hole near surface
Ran 450' of 2" tubing pumped .50 sks. cement through tubing
pulled tubing bailed hole to 30' dumped 2 yds of ready mixed cement to base of celler


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Voth Casing pulling

STATE OF Kansas COUNTY OF Cowley, ss.
Walter Voth (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Walter Voth
715 South A Arkansas City Ks. 67005
(Address)

SUBSCRIBED AND SWORN TO before me this 5 day of Jan, 19 81

My commission expires _____

Notary Public.

FEB - 2 1981

CONSERVATION DIVISION
Wichita, Kansas

NE NE NE
 Sec. 22-289-12W
 Pratt County, Kansas

Inez A. Dowell No. 2

Contractor: Rusco Drilling Co.

Started: February 19, 1944

Finished: March 24, 1944

LOG

Surface soil and sand	0 - 205	
Shale and shells	205 - 393	8-5/8" @ 393' w/150 Sacks
Shale and lime	393 @ 450	
Lime	450 - 1195	
Shale and shells	1195 - 1525	
Lime	1525 - 1955	
Broken lime	1955 - 2155	
Lime	2155 - 2650	
Lime and shale	2650 - 2785	
Lime	2785 - 4200	
Shale	4200 - 4235	
Lime	4235 - 4325	
Shale	4325 - 4345	
Lime	4345 - 4387	
Shale	4387 - 4389	
Porous, sandy dolomite	4389 - 4398	
Shaley sand	4398 - 4405	
Sand	4405 - 4414	
Shale	4414 - 4483	
Shale and dolomitic shells	4483 - 4489	
Dense dolomite	4489 - 4492	

R.T.D. 5 1/2" casing @ 4491' w/
200 sq.

STATE OF KANSAS }
 COUNTY OF PRATT } ss.

I, Vernon Hayes, do hereby certify that the above log is true and correct to the best of my knowledge and belief.


 Superintendent

Subscribed and sworn to before me this 22nd Day of June, 1954.


 Notary Public

My Commission Expires August 29, 1955.