


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plat

Pratt County. Sec. 22 Twp. 29s Rge. 12w E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C E/2 NW SW

Lease Owner Raymond Oil Co.
Lease Name Chitwood Well No. G 1
Office Address One Main Place Suite 900 Wichita 67202
Character of Well (Completed as Oil, Gas or Dry Hole):
Input

Date Well completed 2-15-45 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 12-6-80 19
Plugging completed 12-31-80 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Thompson
Producing formation Depth to top Bottom Total Depth of Well 4438
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4	347'	none
				5 1/2	4413'	1169'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded Hole to 1240' set five sks cement with bailer

Recovered 1169' of 5 1/2" casing

Pumped 10 sks. Gel 4 sks Halls 225 sks. cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Voth Casing Pulling

STATE OF Kansas COUNTY OF Cowley, ss.

Walter Voth

(employee of owner) or (owner or operator)


of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Walter Voth

715 South A Arkansas City, Mo. 67005
(Address)

SUBSCRIBED AND SWORN TO before me this 31 day of Dec, 1980



My commission expires

Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

FEB - 2 1981

CONSERVATION DIVISION
Wichita, Kansas

Fissell No. 4

C - E/2 NW SW
Sec. 22-289-12W
Pratt County, Kansas

Contractor: Corbett-Barbour Drilling Company
Started: January 4, 1945

Finished: February 15, 1945

Drillers Log

Surface Soil and Sand	0' - 40'	
Sand and Shells	185	
Red Bed and Streaks of Lime	355	10-3/4" casing @ 347' w/225 sacks
Red Bed and Shells	390	
Shale and Shells, Red Bed	815	Straight hole test @ 500' - OK
Salt, Shale and Shells	1265	Straight hole test @ 1000' - OK
Shale and Shells, Salt	1680	Straight hole test @ 1500' - OK
Shale and Shells	1715	
Lime and Shale	1790	
Lime	1850	
Broken Lime	1855	
Lime	1877	
Broken Lime	1937	
Lime	2150	Straight hole test @ 2000' - OK
Lime and Shale	2240	
Lime	2485	
Lime and Shale	2795	Straight hole test @ 2500' - OK
Lime	3250	
Broken Lime	3325	
Lime	3830	
Lime and Shale	3885	
Lime	4190	
Chert	4196	
Shale and Chert	4216	
Chert streaks	4227	
Shale	4242	
Lime	4262	
Shale	4267	
Lime	4293	
Sandy Lime	4300	
Lime	4345	
Lime and Chert	4366	
Lime	4414	R. T. D. = 4411' S. L. M. 5-1/2" casing @ 4407' w/400 sacks.

STATE RECEIVED
NOV 26 1960
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
COUNTY OF PRATT) ss.

I, Vernon Hayes, do hereby certify that the above log is true and correct to the best of my knowledge and belief.

Vernon Hayes

Subscribed and sworn to before me this 23rd day of June, 1954.

Das Doube
Notary Public

My commission expires August 29, 1955.

Wue file
[Signature]

xxx 580

March 20, 1957

State Corporation Commission
 211 North Broadway
 Wichita 2, Kansas

Attention: Mr. T. A. Morgan

Re: Chitwood Unit, Pratt County, Kansas

Gentlemen:

Please be advised that Chitwood Unit Well G-1 (Formerly Cities Service Oil No. 4 Fissell) is being used as an input well under Docket No. 47, 551-C (G-4080). Attached is a formation log of this well.

Tabulated below is other information concerning this well.

Location:	990' East and 660' South of West Quarter Corner of Section 22-28S-12W.	
Elevation:	1868' DF	
Top Simpson Sand	4409'	
Simpson Sand Open Hole Interval:	4407' to 4425'	
Casing Information:		
Size	10-3/4"	5 1/2"
Total Length	345'	4407'
Seat Depth	347'	4407'
Condition	Good	Good
Cemented or Mudded	Cemented	Cemented
Estimated Feet Enclosed Cement	345'	1430'
Number sacks Cement Used	225	400

Yours very truly

MONSANTO CHEMICAL COMPANY, UNIT OPERATOR

BER:mc

cc: Mr. J. E. Howell ✓
 Mr. E. L. Maxwell
 file

By Bruce E. Rall

VOTH CASING PULLING

715 South A

ARKANSAS CITY, KANSAS 67005

Phone 442-6278

Customer's
Order No.
& Date

Raymond Oil Co.
One Main Place Suite 900
Wichita Ks. 67202

Refer To
Invoice No.

SOLD
TO

Invoice Date

Lease
and
Well No.

Chitwood G-1
CE/2 NW SW 22 28s 12w
Pratt Co. Kansas

TERMS:

All purchases made on credit during the month are due and payable by the 10th of the following month.
Any balance not paid by the 24th of the following month shall be subject to a FINANCE CHARGE computed at a periodic rate of 1% per month which is an ANNUAL PERCENTAGE RATE of 12%.

QUANTITY	DESCRIPTION	UNIT PRICE	AMOUNT
	Move in and rig up to pull casing	\$ 500.00	
	Pull 1169' of 5 1/2" casing @ 50¢ per ft.	\$ 584.50	
	Tax on \$584.50	\$ 20.46	
	One shot to get casing loose @ \$50.00 per shot	\$ 50.00	
	Five sks. cement to get casing loose @ \$5.00 per sk.	\$ 25.00	
	Three nights out of town for three men at \$ 25.00 ea. per day	\$ 225.00	
	Total	\$ 1404.96	

Thank You

Walter Voth

2-1293

VOTH CASING PULLING

715 South A

ARKANSAS CITY, KANSAS 67005

Phone 442-6278

*Pipe Tally*From Chitwood G-1 On _____ 19____Tally of 5 1/2 Inch Wt. _____ Kind _____Pipe To Raymond Oil Co

	LENGTH		LENGTH		LENGTH		LENGTH		LENGTH		LENGTH	
	Feet	Inch	Feet	Inch	Feet	Inch	Feet	Inch	Feet	Inch	Feet	Inch
1	30	30	31	00								
2	30	40	29	70								
3	32	15	29	70								
4	30	90	30	75								
5	32	00	30	50								
6	31	70	31	90								
7	32	40	32	60								
8	31	50	32	20								
9	31	70	31	40								
10	31	95	30	50								
11	32	35	31	60								
12	31	20	31	85								
13	32	10	31	50								
14	32	10	31	55								
15	32	35	32	40								
16	30	55	31	50								
17	31	50	30	40								
18	30	70	5	90								
19	32	75										
20	31	80										
21	632	40	536	95								

Total No. Joints 38

Tallied By

Total Length 1169 Feet 35 InchesVoth