

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

## WELL PLUGGING RECORD

Pratt County, Sec. 22 E. Twp. 28 Rge. 12 (E) (W)

Location as "NE/CNW/SE/SW" or footage from lines NE NW NE  
Lease Owner Raymond Oil Co., Inc.  
Lease Name Dowell #4 (L-4) Well No. \_\_\_\_\_  
Office Address Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 9/5/72 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 9/12/72 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4411 Feet  
Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	375	none
				5 1/2"	4314'	2515'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole, pushed plug to 4200' and ran 10' sand, dumped 5 sacks of cement. Shot pipe at 3000', pumped 40 barrels of water and broke pressure down to 350 lbs. Ran 4 sacks mud and 2 sacks hulls. Pumped 40 barrels of oil behind mud and hulls and displaced it behind pipe. Worked pipe, shot at 2512' and pulled 81 joints. Bailed fluid to 250' and set 10' rock bridge and dumped 4 yards ready mix.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 20 1972  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.  
Address CHASE, KANSAS

STATE OF Kansas COUNTY OF Rice, ss.

Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Chase, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of September, 19 72

MARGARET MELCHER  
NOTARY PUBLIC  
Rice County, Kansas  
My Commission Expires  
Feb. 15, 1975

My commission expires

Margaret Melcher  
Notary Public.

*Howell*

*PC 5*  
*de 1*

*will file*

xxx 580

April 21, 1958

RECEIVED  
STATE CORPORATION COMMISSION  
APR 22 1972  
CONSERVATION DIVISION  
Wichita, Kansas

State Corporation Commission  
211 North Broadway  
Wichita 2, Kansas

Attention: Mr. Jewell M. Ogden

Re: Chitwood Unit, Pratt County, Kansas

Gentlemen:

Please be advised that Chitwood Unit Well No. L-4 (Formerly Skelly Oil Company Dowell No. 4) is being used as an input well under Pocket No. 47, 551-C (C-4080).  
Attached is a formation log of this well.

Tabulated below is other information concerning this well.

Location:	660' from North Line and 990' from West Line of the Northwest Quarter of Section 22-28S-12W.	
Elevation:	1875' DF	
Top of Simpson Sand	4410'	
Simpson Sand Open Hole Interval:	4411' to 4429'	
Casing Information:		
Size	8-5/8"	5 1/2"
Total Length	372'	4447'
Seat Depth	375'	4411'
Condition	Good	Good
Cemented or Mudded	Cemented	Cemented
Estimated Feet Enclosed Cement	372'	1354'
Number Sacks Cement Used	150	200

Yours very truly

MONSANTO CHEMICAL COMPANY, UNIT OPERATOR

BER:MC:mc  
cc Mr. J. E. Howell  
Mr. E. L. Maxwell  
Mr. Vernon Hayes  
file

By Bruce E. Rell