

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Pratt County, Sec. 22 Twp. 28 Rge. 12 (E) (W)

Location as "NE/CNW/SE" or footage from lines SE NE NE
Lease Owner Raymond Oil Co., Inc.
Lease Name Chitwood K#6 Well No. _____
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 10/24/69 _____ 19____
Plugging completed 10/30/69 _____ 19____
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Warren
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4417 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8 | 365' | none |
| | | | | 5 1/2" | 4405' | 2136' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 4417', ran sand to 4390' and dumped 5 sacks of cement. Loaded hole with water, shot pipe at 3192', 3104', 2987', pumped in 2 sacks hulls and 4 sacks mud. Spotted 40 barrels of oil behind pipe, pumped in 40 barrels of water, broke pressure to 300 lbs. Mixed and dumped in 3 sacks hulls and 6 sacks mud. Tried to circulate with 200 barrels of water. Shot pipe at 2798, 2607, 2497, 2312, 2216, and 2130', ~~we~~ worked pipe loose and pulled 70 joints. Bailed fluid down to 260' and set 10' rock bridge, dumped 25 sacks cement, mudded to 40', set 10' rock bridge and dumped 10 sacks of cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
NOV 4 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn, on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
CHASE, KANSAS

Subscribed and Sworn to before me this 31st day of October, 1969

[Signature]
Notary Public.

My commission expires 2/15/71

