


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely/
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD



Pratt County, Sec 22 Twp 28 Rge. 12 (E) (W)
Location as "NE/CNW/SW" or footage from lines NE SE NE
Lease Owner Raymond Oil Co., Inc.
Lease Name Chitwood J#6 Well No.
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 2/27/70 19
Plugging completed 3/3/70 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein
Producing formation Depth to top Bottom Total Depth of Well 4415 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	STATE CORPORATION COMMISSION			8-5/8	360	none
	RECEIVED			5 1/2	4408'	2005'
	MAR 11 1970					
	CONSERVATION DIVISION					
	Wichita, Kansas					


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 4415', ran sand and 5 sacks of cement. Loaded hole with water, shot pipe at 3220', pumped load of water, 3 sacks hulls, 6 sacks mud, got 800 lb. pressure. Pumped load oil and 2 loads water. Worked pipe to 23" tension, pumped two loads water, worked pipe to 24" tension, shot pipe at 3103', pumped load water, shot pipe at 3004', 2902', 2808', 2707', 2617', 2526', 2420', 2302', 2200', 2101', 2000', worked pipe loose and pulled 63 joints. Bailed hole to 250', set 10" rock bridge and ran 25 sacks of cement. Mudded hole to 40', set 10" rock bridge and ran 10 sacks of cement. Tallied pipe.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) Noel Knight
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN to before me this 4th day of March, 1970

My commission expires 2/15/71 Notary Public.

