


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County, Sec. 22 Twp. 28S Rge. 12W (E) (W)

Location as "NE/CNW/SW" or footage from lines C NE/4 SE/4 SE/4  
Lease Owner Raymond Oil Co., Inc.  
Lease Name Chitwood F#6 Well No.  
Office Address Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 12/8/69 19  
Plugging completed 12/12/69 19  
Reason for abandonment of well or producing formation depleted.

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Justice  
Producing formation Depth to top Bottom Total Depth of Well 4484 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	322'	none
				5 1/2"	4441'	2300'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 4484', ran sand to 4375' and ran 5 sacks of cement. Shot pipe at 3297', spotted 40 barrels oil, shot pipe at 2988', 2840', 2687', 2541', 2400', 2307', worked pipe loose and pulled 70 joints. Bailed hole to 250', set 10' rock bridge and ran 25 sacks of cement. Mudded hole to 40', set 10' rock bridge and ran 10 sacks of cement. Tallied pipe.

PLUGGING COMPLETE.


RECEIVED  
STATE CORPORATION COMMISSION  
DEC 17 1969  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.  
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
CHASE, KANSAS (Address)

Subscribed and Sworn to before me this 15th day of December, 1969



Margaret Melcher  
Notary Public.

