

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

RECEIVED Form CP-4
STATE CORPORATION COMMISSION Rev. 12-15-80

SEP 2 1982

WELL PLUGGING RECORD

CONSERVATION DIVISION
Wichita, Kansas

Give All Information Completely
Make Required Affidavit

COUNTY Pratt SEC. 22 TWP. 28 RGE. 12W E/W
Location as in quarters or footage from lines:
SW NE NE

Locate Well
correctly on above
Section Pratt.

Lease Owner Raymond Oil Company, Inc.
Lease Name Hillard G-5 Well No. _____
Office Address One Main Place Suite 900 Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 8-18-82
Plugging completed 8-27-82
Reason for abandonment of well or producing formation
Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J.H. Metz

Producing formation _____ Depth to top _____ bottom T.D. 3187'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	344'	none
				4-1/2"	2790'	2006'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged off bottom with sand to 2610' and ran 4 sacks cement. Shot casing @2216',
2144' and 2003', pulled a total of 63 joints of 4-1/2" casing. Plugged well with
4 sacks hulls, 25 sacks 50/50 pos, 4% gel, 3% cc, 20 sacks gel, 1 sacks hulls,
8-5/8" plug, 125 sacks 50/50 pos, 4% gel, 3% cc.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347 Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 31st. day of August, 1982

My Commission expires:



Irene Hoover
Notary Public.

Operator Raymond Oil Company, Inc		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. G-5	Lease Name Hillard	Gas
S 22 T 28 R 12 E W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 - 45/45/45/45	2659	2661	Log Tops	
Strong blow - Gas to surface for 5"				
Gauged thru 1-1/2" opening - blew muddy spray 6" after 2nd opening			Red Eagle	2507
Rec. 530' gassy mud			Indian Cave	2632
FP 226-397 - ISIP - failed - FP 397-411 - FSIP 964			LTD	3180
First Opening				
303 Mcf 10"				
654 " 20"				
814 " 30"				
863 " 40"				
863 " 45"				
Second Opening				
953 Mcf 10"				
995 " 20"				
995 " 30"				
995 " 40"				
1,036 " 45"				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	RAYMOND OIL COMPANY, INC.	
	<i>Wm. M. Raymond</i>	
	Wm. M. Raymond Signature	
	President	
	Title	
	September 9, 1975	
	Date	