

15-129-20124 0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Morton County. Sec. 15 Twp. 31 Rge. 41W (E) (W)

Location as "NE/CNW/SW" or footage from lines G NW

Lease Owner Messman-Rinehart Oil Co.

Lease Name Vratil Well No. 1

Office Address 1432 Wichita Plaza Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Gas

Date well completed 3/17 19 58

Application for plugging filed 2/26 19 64

Application for plugging approved 4/3 19 64

Plugging commenced 6-17 19 64

Plugging completed 6-19 19 64

Reason for abandonment of well or producing formation Non-commercial gas production

If a producing well is abandoned, date of last production April 1964

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5475 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1500	None
				4 1/2	5473	3210

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Cement bottom perforations off with 20 sacks cement.  
Stop plug at 5300'. Fill hole with mud to 700' and pump 35 sks cement 700' to 600'. Fill with Mud to 45' and put 15 sacks cement 45' to base of cellar. Have welder cut 8 5/8 casing off and weld cap on same.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 2 1964

7-2-64

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargents Casing Pulling Service

Address Box 506 Liberal Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

J. A. Gilliland (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Gilliland

1432 Wichita Plaza Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 1st day of July, 19 64

Barbara J. Scott Notary Public

My commission expires December 1, 1964

# WELL LOG

15-129-26424 0000

COMPANY MESSMAN-RINEHART OIL COMPANY

SEC. 15 T. 31S. 41W

FARM VRATIL UNIT NO. 1


LOC. C-NW/4

TOTAL DEPTH 5580'

COUNTY Morton Co., Kansas

COMM. January 19, 1958 COMP. February 17, 1958

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8.5/8" @ 1500' W/1000 sax.  
4 1/2" @ 5555.03' W/150 sax.

ELEVATION 3384' DF

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

10	Sand
200	Surface clay & sand
480	Red bed
640	Red bed, shale & shells
700	Shale & shells
1067	Red bed
1140	Shale & shells
1392	Shale, red bed & anhydrite
1478	Sand & lime
1502	Lime & shale
1995	Shale & shells
2490	Shale
5124	Lime & shale
5368	Shale
5420	Shale & sand
5492	Shale
5514	Shale & sand
5580	Lime
5580	I. D.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 2 1964

CONSERVATION DIVISION  
Wichita, Kansas

State of KANSAS }  
County of BARTON } ss:

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 VRATIL UNIT well

*Verne A. Morris*

Subscribed and sworn to before me this 4th day of March 19 58

My Commission Expires: November 12, 1958

*Boan*  
NOTARY PUBLIC

15-129-20424-0000

COMPLETION DATA

Messman-Rinehart Oil Company  
No. 1 Vratil Unit  
Ctr. NW/4, Section 15-31S-41W  
Morton County, Kansas

- 2/26/58 - M.I.C.T.  
3/3/58 - Perf. 5499-5503' w/3<sup>s</sup> per ft., Swb. rate - 30 GWPH (final gauge)  
Set plus @ 5480'  
3/4/58 - Perf. 5392-5398' w/3<sup>s</sup> per ft., gauged 350,000 cfg  
3/6/58 - Frac w/10,000 gal. gel kerosene  
Total load 324 bbls., Fed in @ top pressure of 2600# at rate  
of 13 bbls/min., Broke to 800# in 5", swbd. 80 bbls. & shut  
down for weather  
3/8/58 - Testing 1,000,000 cfg and 1.25 BFPH, 144 bbls. of load to recover  
3/17/58 - Last hour of testing, made .42 bbls. fluid (.24 BW), producing  
at the rate of 1,000,000 cfg  
Shut in awaiting connection.

MESSMAN-RINEHART OIL COMPANY

RECEIVED  
STATE CORPORATION COMMISSION

JUL 2 1961

CONSERVATION DIVISION  
Wichita, Kansas