

15-129-16175-0006

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Locate well correctly on above
Section Plat

Morton County, Sec. 20 Twp. 31S Rge. 41 (E) (W) X
Location as "NE/CNW&SW" or footage from lines. NW NE SW
Lease Owner. Thomas Petroleum
Lease Name. Harrison Well No. 1
Office Address. Box 1177 Liberal, Kansas 67901
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed. 5-2-61 19
Application for plugging filed. 4-2 1975
Application for plugging approved. 4-3 1975
Plugging commenced. 4-3 1975
Plugging completed. 4-4 1975
Reason for abandonment of well or producing formation. Non-productive
If a producing well is abandoned, date of last production. July 1971
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well. Clarence Thomas
Producing formation. Wabunsee Depth to top 2856 Bottom 2897 Total Depth of Well 5350
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1432	none
				4 1/2	2960	2022
				2 3/8	2844	2844

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pump 1 sk. of hulls & 10 sks. of cement from 2850 to 2750
Pump 25 sks. of cement from 900 to 800
Put 10 sks. of cement from 33 to 3

RECEIVED
STATE CORPORATION COMMISSION

1975 4 1975
4-24-75
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor. Sargents Casing Pulling Service Kansas No. 511
Address. Box 506 Liberal, Kansas 67901

STATE OF Kansas COUNTY OF Seward ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Debra L. Luck
Box 1177 Liberal, Kas.
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of April, 1975

My commission expires 11-5-78
Marlene Keating
Notary Public.

STATE NOTARY PUBLIC
MARLENE KEATING
Seward County, Ks.
My Comm. Exp. Nov. 5, 1978

THOMAS & BREWER
HARRISON #1

RTD 5350'

Commenced 3/12/61
Completed 4/5/61

15-129-10175-0000

NW NE SW Section 20-31-41W
Morton County, Kansas

CONTRACTOR: Bennett & Roberts Drilling Co.

Set 8 5/8" @ 1432' w/750 sx cmt
Set 4 1/2" @ 2960' w/100 sx cmt

Surface Soil & Sand	70
Sand & Clay	130
Shale	160
Lime & Shale	185
Shale & Shells	370
Sand & Sandstone	430
Red Bed	660
Anhydrite	685
Red Bed	926
Red Bed & Anhyd. Streaks	1025
Anhydrite	1100
Sand & Red Bed	1243
Anhydrite & Sandstone	1321
Red Bed	1499
Anhydrite	1510
Anhydrite & Red Bed	1540
Shale & Shells	1800
Shale	1998
Red Bed & Lime Streaks	2095
Shale	2167
Shale & Lime	3228
Lime & Chalk	3373
Lime & Shale	3475
Lime & Chalk Streaks	3611
Lime & Chalk	3684
Lime	4024
Lime & Shale	4354
Lime	4580
Shale	4708
Lime & Shale	5180
Shale	5240
Lime & Shale	5350

RECEIVED
STATE CORPORATION COMMISSION
APR 11 3 19/61
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
RUSSELL COUNTY) SS

I hereby certify that the above information is correct to the best of my knowledge.

BENNETT & ROBERTS DRILLING COMPANY

By

Mildred B. B. B.

Subscribed and sworn to before me this 10th day of April, 1961

Carol L. L.

Notary Public

My Commission Expires 6/17/62