

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER. 15-129-20,781-000

LEASE NAME Randall McComb

WELL NUMBER 24-1

4950 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 24 TWP. 31 SRGE. 41 (XXX)(W)

COUNTY Morton

Date Well Completed 1-15-86

Date Recompleted 3-8-88

Plugging Commenced 5-9-88

Plugging Completed 5-11-88

COPY

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR J. M. Huber Corporation

ADDRESS 7120 I-40 West, Suite 232, Amarillo, TX 79106

PHONE#(806) 353-9837 OPERATORS LICENSE NO. 5703

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? Dodge City (Mr. Glenn Barlow w/KCC on location)

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Morrow "G" Depth to Top 5316' Bottom 5400' RECEIVED 5550'

Show depth and thickness of all water, oil and gas formations.

STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

AUG 11 1988

Formation	Content	From	To	Size	Put In	Pulled out
Morrow "G"	Oil	5316'	5400'	20"	30'	CONSERVATION DIVISION
				8-5/8"	1584'	Wichita Kansas
				5-1/2"	5549'	0
						482'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Set CIBP @ 5240', capped w/2 sx cmt, TOC @ 5220'. Load 5-1/2" csg w/88 bbls 9.5 ppg mud. Cmt 5-1/2" csg @ 500'. Pulled 11 its (482'). Set 50 sx Class H cmt plug from 1650' to 1550'. Set 50 sx Class H cmt plug 750' to 650'. Filled hole w/9.5# mud. Set 10 sx Class H cmt plug 40' to 3'. Cut off 8-5/8" 3" BGL. Weld on steel cap.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P. O. Box 506, Liberal, Kansas 67901

STATE OF TEXAS COUNTY OF POTTER, ss.

Robert R. Glenn, District Production Manager (Employee of Operator) ~~XXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 7120 I-40 West, Suite 232  
 Amarillo, Texas 79106

SUBSCRIBED AND SWORN TO before me this 12th day of May, 19 88

Deniese L. Barnett  
 Notary Public  
 Deniese L. Barnett

Commission Expires: 6-26-89

