

LEASE NAME Hanke Trust

WELL NUMBER 1  
1650 Ft. from S Section Line  
660 Ft. from E Section Line

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Clyde M. Becker

SEC. 32 TWP. 31 RGE. 41 (E) or (W)

ADDRESS 212 First National Bldg., Ponca City, OK 74601

COUNTY Morton

PHONE# (405) 765-8788 OPERATORS LICENSE NO. 07344

Date Well Completed 7-27-92

Character of Well D & A

Plugging Commenced 7-27-92

(Oil, Gas, O&A, SMD, Input, Water Supply Well)

Plugging Completed 7-27-92

The plugging proposal was approved on 7-27-92 (date)

by \_\_\_\_\_ (KCC District Agent's Name).

Is ACC-1 filed? Yes if not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1513	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each section. Spotted 50 sxs @ 1540', 40 sxs @ 700', 10 sxs @ 40', 10 sxs in rat hole, 10 sxs in mouse hole.

Name of Plugging Contractor Halliburton License No. \_\_\_\_\_

Address Liberal, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Clyde M. Becker

STATE OF Oklahoma COUNTY OF Kay, ss.

Clyde M. Becker (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Clyde M. Becker  
(Address) 212 First National Bldg.  
Ponca City, OK 74601

SUBSCRIBED AND SWORN TO before me this 17th day of August 1992

Maureen Holme  
Notary Public

My Commission Expires: 11-14-92

USE ONLY ONE SIDE OF EACH FORM

RECEIVED  
AUG 19 1992

DRILLERS LOG

15-129-21134-0000

CLYDE M. BECKER  
HANKE TRUST #1  
SECTION 32-T31S-R41W  
MORTON COUNTY, KANSAS

COMMENCED: 07-17-92  
COMPLETED: 07-27-92

SURFACE CASING: 1507' OF 8 5/8"  
CMTD W/585 SX LT "C", 2% C.C.,  
1/4#/SX FLO-CELE; TAILED IN W/  
150 SX "C", 2% C.C., 1/4#/SX FLO-CELE

FORMATION	DEPTH
SURFACE HOLE	0-1513
RED BED	1513-1620
SHALE	1620-2125
LIME & SHALE	2125-2830
SHALE & LIME	2830-3130
LIME & SHALE	3130-3405
LIME, SHALE & LANSING	3405-3859
SHALE & LIME	3859-4790
LIME, SHALE & MORROW	4790-5023
MORROW	5023-5276
LIME & SHALE	5276-5390 RTD


I DO HEREBY CERTIFY THAT THE FOREGOING STATEMENTS ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

CHEYENNE DRILLING, INC.

*A.J. Jacques*  
A.J. JACQUES

STATE OF KANSAS :ss:

SUBSCRIBED AND SWORN TO BEFORE ME THIS 28TH DAY OF JULY, 1992.



*Becky J. Whetstone*  
BECKY J. WHETSTONE, NOTARY PUBLIC

RECEIVED  
STATE CORPORATION COMMISSION

AUG 19 1992

CONSERVATION DIVISION  
Wichita, Kansas