

STATE OF KANSAS
STATE CORPORATION COMMISSION
201 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-129-10089-0000

API NUMBER N/A

LEASE NAME Mitchell

WELL NUMBER #1

SPOT LOCATION 3969' N. of S. Line,
1391.8' E. of W. Line,

SEC. 36 TWP. 31S RGE. 41W (E) or (W)

COUNTY Morton

Date Well Completed 9-3-82

Plugging Commenced 8:00 a.m. 6-27-84

Plugging Completed 6:00 p.m. 6-28-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR DACO, Inc
TRAVIS H. DAVIS GAS ACCT.

ADDRESS P. O. Drawer 3010, Borger, TX 79008-3010

PHONE # (806) 273-7321 OPERATORS LICENSE NO. 6416
206845

Character of Well Gas
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? Dist. #1, 302 West McArtor, Dodge City, KS 67801

Is ACO-1 filed? N/A If not, is well log attached? N/A

Producing formation Morrow Depth to top 5283' bottom 5295' T.D. 5700'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Morrow	Gas	5283'	5295'	5 1/2"	5674'	1563.90'
Hugoton	Gas	2220'	1514'	8 5/8"	1514'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Set CIBP @ 5250' with 5 sks. common cement on top, load hole with 9.5# mud, set CIBP @ 2290', run tubing in, mix & pump 20 sks. common cement, pull tubing, well on 5 1/2" collar, tag cement @ 2063', shoot 5 1/2" @ 1567', break circulation with 20 bbls. 9.5# mud, mix & pump 75 sks. common cement from 1567' to 1350' with 32 bbls. disp., pull up to 750', mix & pump 40 sks. common cement from 750' to 615' with 15 bbls. disp, tag, pull up to 40', mix & pump 10 sks. common cement from 40' to 4'.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Daco, Inc. License No. 6416
Address P. O. Drawer 3010, Borger, TX 79008-3010

STATE OF TEXAS COUNTY OF HUTCHINSON, ss.

JACK F. PAINTER (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack Painter
(Address) P.O. Drawer 3010, Borger, TX 79008-3010

RECEIVED
STATE CORPORATION COMMISSION

JUL 27 1984

SUBSCRIBED AND SWORN TO before me this 24th day of July, 1984

CONSERVATION DIVISION
My Commission Expires 8-3-85

Judy E. Stark
Notary Public