

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-119-20 ³⁸⁴⁻⁰⁰⁰⁰₃₈₆

LEASE NAME HEINSON

WELL NUMBER 1-27

2640 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 27 TWP. 33 RGE. 28 (E) or (W)

COUNTY Meade

Date Well Completed ^{P&A} 12-24-85

Plugging Commenced 12-21-85

Plugging Completed 12-24-85

LEASE OPERATOR Mesa Petroleum Co.

ADDRESS P.O. Box 2009, Amarillo, Texas 79189

PHONE# (806) 378-1000 OPERATORS LICENSE NO. 5575

Character of Well P&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Chester Depth to Top 5887 Bottom 5928' T.D. 6030'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Chester	gas	5887	5928	8 5/8	1513'	-
				4 1/2	6001'	2961'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Set CIBP @ 5830' w/20' cement on top. loaded hole with 9 ppg mud, shot off 4 1/2" csg @ 3040'; spot 50 sx cement plug 1363-1563'; spotted 25 sx cement plug 300-600'; set solid plug @ 40' and dump 10 sx cement on top. Cut csg 3' below GL - weld on dry hole marker.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pullers License No. 6547

Address Box 506, Liberal, Kansas 67901

STATE OF Texas COUNTY OF Potter, ss.

Carolyn L. Cummings (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Carolyn Cummings

(Address) P.O. Box 2009, Amarillo, TX 79189

SUBSCRIBED AND SWORN TO before me this 2nd day of January, 19 86

My Commission Expires: 8-6-89

STATE CORPORATION COMMISSION

XC: KCC (0+1), WF, CR, Reg., Acctg, Land, Expl., Partners

JAN 6 1986
1-6-1986
CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 08-84

RECEIVED
AMARILLO PRODUCTION

JUN 28 1979

DRILLERS LOG
HEINSON NO. 1-27

JLF		GD	
SD		BC	
		TLS	

CASING RECORD: 8-5/8" set @ 1513' w/800 sax cement
 TOTAL DEPTH: 6030'

OPERATOR: Mesa Petroleum Co.
 CONTRACTOR: Sage Drilling Co., Inc.
 COMMENCED: June 6, 1979
 COMPLETED: June 20, 1979


DESCRIPTION: 2640' FNL&660' FWL
 Sec. 27-33S-28W
 Meade County,
 Kansas.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Red Bed	0	1540	
Red Bed & Shells	1540	2280	
Shale	2280	2555	
Lime & Shale	2555	2680	
Dolomite & Shale	2680	3040	
Shale & Lime	3040	3272	
Lime & Shale	3272	5782	Ran DST#1;
Lime & Shale	5782	5870	Ran DST#2;
Lime & Shale	5870	6030	Logged Hole; 4 1/2" set @ 6001' w/250 sax cement

I certify that this is a true and correct copy of the log on the above captioned well to the best of my knowledge.

SAGE DRILLING CO., INC.

By John R. Bartholomew
John R. Bartholomew



Subscribed and sworn to before me this 25th day of June, 1979.

Louise K. Whitted
Louise K. Whitted, Notary Public
Wichita, Kansas

My commission expires:
November 26, 1982.
XC: Denver 8-1-79

STATE COMMISSION
DEC 16 1985
CORRELATION DIVISION
Wichita, Kansas