

LEASE OPERATOR Samedan Oil Corporation

ADDRESS 9400 N. Broadway, Ste. 700, Oklahoma City, OK 73114

PHONE#(405) 475-2000 OPERATORS LICENSE NO. 04570

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4/30/97 (date)

by Mike at Dodge City (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Morrow Depth to Top 5602 Bottom 5632 T.O. 5750

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Morrow	Oil	5602	32	20"	55'	0
				8 5/8"	1538'	0
				4 1/2"	5750'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Pump 35 sxs 60/40 cmt w/6% gel + 100# cotton seed hulls @ 13.2 ppg into Morrow perfs 5602' - 5632' leaving 700' cmt in 2 3/8" tbgs. Displaced w/9.2 ppg plug mud. Loaded hole w/9.2 36 vis plug mud. RU Howco mix and pump balance plug 25 sxs 60/40 w/6% gel @ 13.2 ppg, displaced w/9.2 ppg plug mud. Plug balanced. Perf csg. @ 550'. Pump 58 bbls mud, had good circulation. Set cement retainer @

Name of Plugging Contractor Double T Tool and Supply d/b/a Jet Well Service License No. 31646 OVER

Address P. O. Box 607, Perryton, Texas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Samedan Oil Corporation

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Debbie Kerr (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Debbie Kerr

(Address) 9400 N. Broadway, Suite 700

Oklahoma City, Oklahoma 73114

SUBSCRIBED AND SWORN TO before me this 5th day of May, 19 97

Karen Lennox
 Notary Public

My Commission Expires: March 16, 1999

USE ONLY ONE SIDE OF EACH FORM

503'. Mix and pump 100 sxs 60/40 cmt w/6% gel at 13.2 ppg. Had good circ up surface csg. Cmt did not circ. Sting out of retainer leaving 2 sxs cmt on retainer. Cut off 8 5/8" and 4 1/2" csg @ 3' below ground level. Top off 4 1/2" csg annulus w/43 sxs 60/40 poz + 6% gel @ 13.1 ppg, annulus full. Mix and pump 7 sxs same cmt in 4 1/2" csg from 126' to 3'. Cap with plate bearing Mohler #11, Samedan Oil, 5/2/97. Restore location.