

STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

K.A.R.-82-3-117

API NUMBER 15-119-20,430-0000

LEASE NAME Mohler Unit

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 13

1320 Ft. from S Section Line

2420 Ft. from E Section Line

LEASE OPERATOR Samedan Oil Corporation

SEC. 30 TWP. 33S RGE. 28 (E) or (W)

ADDRESS 9400 N. Broadway, Suite 700, Oklahoma City, OK 73114

COUNTY Meade

PHONE# (405) 475-2000 OPERATORS LICENSE NO. 04570

Date Well Completed 10-20-80

Character of Well Oil

Plugging Commenced 6-27-97

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7-16-97

The plugging proposal was approved on 6-24-97 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? N/A

Producing Formation Morrow Depth to Top 5640 Bottom 5654 T.D. 5752

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Morrow	Oil	5640	5645	8 5/8	1709	0
				5 1/2	5752	2620'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Fill hole from surface to top perf at 5640' with 120 bbls 9.5 ppg 40 vis mud. Set CIBP at 5590'. Dump 2 sacks cement on top of plug. Set 80 sack cement plug from 1812' to 1523'. Displace with 36 bbls 40 vis 19.5 ppg mud. Set 40 sack cement plug from 665' to 520'. Displace with 13 bbls 9.5 ppg 40 vis mud. Set 10 sacks cement plug from 34' to 4'. Weld on I.D. plate. Recovered 62 fts. (2620') of 5-1/2" casing.

Name of Plugging Contractor Sargent's Casing Pullers License No. 6547

Address P.O. Box 506, Liberal, Kansas 67705-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Samedan Oil Corporation

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Debbie Kerr (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Debbie Kerr

9400 N. Broadway, Suite 700

(Address) Oklahoma City, OK 73114

SUBSCRIBED AND SWORN TO before me this 17th day of July, 19 97

Karen Lenoir
Notary Public

My Commission Expires: March 16, 1999

USE ONLY ONE SIDE OF EACH FORM