

STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

K.A.R.-82-3-117

API NUMBER 15-119-20,586-0000

LEASE NAME Mohler Unit

WELL NUMBER 8

2310 Ft. from <sup>N</sup>/<sub>S</sub> Section Line

330 Ft. from <sup>W</sup>/<sub>E</sub> Section Line

SEC. 29 TWP. 33S RGE. 28 (E) or (W)

COUNTY Meade

Date Well Completed 11-8-82

Plugging Commenced 6-27-97

Plugging Completed 7-10-97

6/24/97 (date)

LEASE OPERATOR Samedan Oil Corporation

ADDRESS 9400 N. Broadway, Ste. 700, Oklahoma City, OK 73114

PHONE# (405) 475-2000 OPERATORS LICENSE NO. 04570

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6/24/97 (date)  
by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? N/A

Producing Formation Morrow Depth to Top 5608 Bottom 5618 T.D. 5919

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Morrow	Oil	5588	5651	8 5/8	1510	0
				5 1/2	5918	4255

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set  
Fill hole from surface to top perf at 5608' with 125 bbls. 9.5 ppg 40 vis. mud. Set CIBP at 5530' with 2 sks cement on plug. Set 80 sks. cement plug from 1620'-1330'. Displace with 31 bbls. 9.5 ppg. 40 vis. mud. Set 40 sacks cement plug from 650'-505'. Displace with 12 bbls. 9.5 ppg. 40 vis. mud. Set 10 sks. cement plug from 34'-4'. Weld on I.D. plate. Recovered total 103 jts. (4255') 5 1/2" casing.

Name of Plugging Contractor Sargent's Casing Pullers License No. 6547

Address P. O. Box 506, Liberal, Kansas 67705-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Samedan Oil Corporation

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Debbie Kerr

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Debbie Kerr

9400 N. Broadway, Suite 700

(Address) Oklahoma City, OK 73114

SUBSCRIBED AND SWORN TO before me this 14th day of July, 19 97

Karen Lennex  
Notary Public

My Commission Expires: March 16, 1999

USE ONLY ONE SIDE OF EACH FORM