

LEASE NAME Mohler Unit

WELL NUMBER 17

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

986 Ft. from S Section Line

230 Ft. from ~~E~~ Section Line

SEC. 29 TWP. 33S RGE. 28 (E or W)

LEASE OPERATOR Samedan Oil Corporation

COUNTY Meade

ADDRESS 9400 N. Broadway, Suite 700, Oklahoma City, OK 73114

Date Well Completed 3-31-94
6-21-82

PHONE# (405) 475-2000 OPERATORS LICENSE NO. 04570

Plugging Commenced 6-27-97

Character of Well Oil

Plugging Completed 1-14-97

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-24-97 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? N/A

Producing Formation Morrow Depth to Top 5600 Bottom 5632 T.D. 2350

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Morrow	Oil	5600	5632	8 5/8"	1521	0
				5 1/2"	5747	2625

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Fill hole from surface to top perf at 5600' with 125 bbls. 9.5 ppg 40 vis. mud. Set CIBP at 5550' and dump 2 sacks cement on top. Set 80 sack cement plug from 1620'-1330'. Displace with 30 bbls. 9.5 ppg 40 vis. mud. Set 40 sack cement plug from 650'-505'. Displace with 12 bbls. 9.5 ppg 40 vis. mud. Set 10 sack cement plug from 34'-4'. Weld on T.D. plate. Recovered 62 jts. (2625') 5 1/2 casing.

Name of Plugging Contractor Sargent's Casing Pullers License No. 6547

Address P.O. Box 506, Liberal, KS 67705-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Samedan Oil Corporation

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Debbie Kerr

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: that I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Debbie Kerr
9400 N. Broadway, Suite 700

(Address) Oklahoma City, OK 73114

SUBSCRIBED AND SWORN TO before me this 15th day of July, 19 97

Karen Lennox
Notary Public

My Commission Expires: March 16, 1999

USE ONLY ONE SIDE OF EACH FORM