

STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

K.A.R.-82-3-117

API NUMBER 15-119-20,556-0001

LEASE NAME Mohler Unit

WELL NUMBER 12

2310 Ft. from S Section Line  
W  
330 Ft. from E Section Line

SEC. 29 TWP. 33S RGE. 28 (X) or (W)

LEASE OPERATOR Samedan Oil Corporation

ADDRESS 9400 N. Broadway, Suite 700, Oklahoma City, OK 73114 COUNTY Meade

PHONE# (405) 475-2000 OPERATORS LICENSE NO. 04570

Date Well Completed 3/29/82

Character of Well Water Injection Well

Plugging Commenced 6/27/97

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7/3/97

The plugging proposal was approved on 6/24/97 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? N/A

Producing Formation Morrow Depth to Top 5591 Bottom 5618 T.D. 5792

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Morrow	Oil	5591	5618	8 5/8"	1527'	0
				4 1/2"	5791'	+/-910'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set  
Fill hole from surface to top perf @ 5591' with 90 bbls 9.5 ppg 40 vis mud. Set CIBP @ 5530'.

Dump 2 sks cmt on plug. Recovered +/- 910' of 4 1/2" casing. Circulate hole @ 1598' w/ 40 bbls 9.5 PPG- 40 vis mud. Spot balanced cmt plug from 1598' - 1334' with 80 sks Class "H" Cement. Displace cement w/ 21 bbls mud. Spot balanced cement plug from 650'-548' with 40 sacks Class "H" Cement. Displace with 8 bbls mud. Set cement-plug from 34'-4' with 10 sacks cement. Cut off surface casing

Name of Plugging Contractor Sargent's Casing Pullers License No. 6547 (over)

Address P. O. Box 506, Liberal, Kansas 67705-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Samedan Oil Corporation

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Debbie Kerr

(Employee of Operator) or (Operator) o

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Debbie Kerr

9400 N. Broadway, Suite 700

(Address) Oklahoma City, OK 73114

SUBSCRIBED AND SWORN TO before me this 8th day of July, 19 97

Patricia R. Bady  
Notary Public

My Commission Expires: 4-18-99

USE ONLY ONE SIDE OF EACH FORM

(from front page)

4' below ground. Weld on name plate. Plugging witnessed by KCC rep. Scott Alberg.