

STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

K.A.R.-82-3-117

API NUMBER 15-119-20,602 - ~~000~~

LEASE NAME Mohler Unit

WELL NUMBER 16

4950 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 31 TWP. 33S RGE. 28 (X) or (W)

COUNTY Meade

Date Well Completed 3-5-83

Plugging Commenced 6-27-97

Plugging Completed 7-1-97

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Samedan Oil Corporation  
ADDRESS 9400 N. Broadway, Ste. 700, Oklahoma City, OK 73114

PHONE# (405) 475-2000 OPERATORS LICENSE NO. 04570

Character of Well Water Injection Well

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6/24/97 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached?

Producing Formation Morrow Depth to Top 5608 Bottom 5650 T.D. 5900

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Morrow	Oil	5608	5650	8 5/8"	1483'	0'
				4 1/2"	5875'	2521'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set  
Pump 90 bbls 9.5 ppg 40 vis mud & fill hole from surface to top perf @ 5608'. Set CIBP @ 5530'.  
Dump 2 sxs cmt on plug. Circulate hole w/40 bbls 9.5 ppg 40 vis plug mud. Set cement plug from 1533' to 1218' with 80 sxs Class "A" cement. Displace cement w/20 bbls 9.5 ppg 40 vis mud. Set cement plug from 650' to 518' with 40 sxs Class "A" cement. Displace cement w/8 bbls 9.5 ppg 40 vis mud. Set cement plug from 34' to 4' with 10 sxs Class "A" cmt. Cap well & weld on name plate.  
Puller total 2521' (64 jts) of 4 1/2" casing.

Name of Plugging Contractor Sargent's Casing Pullers License No. 65473

Address P. O. Box 506, Liberal, Kansas 67705-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Samedan Oil Corporation

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Debbie Kerr

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Debbie Kerr  
9400 N. Broadway, Suite 700  
(Address) Oklahoma City, OK 73114

SUBSCRIBED AND SWORN TO before me this 3rd day of July, 19 97

Karen Penney  
Notary Public

My Commission Expires: March 16, 1999

USE ONLY ONE SIDE OF EACH FORM