

LEASE NAME Wiens

WELL NUMBER 1-35

SPOT LOCATION SW-NW

SEC. 35 TWP. 33 RGE. 28 (or (W))

COUNTY Meade

Date Well Completed _____

Plugging Commenced 5-10-90

Plugging Completed 5-15-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Ensign Operating Co.

ADDRESS 621 Seventeenth St., Ste 1800, Denver, CO 80293

PHONE # (303) 293-9999 OPERATORS LICENSE NO. 4782

Character of Well Gas
(Oil, Gas, D&A, SHD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation Council Groves Depth to top 3119 bottom 3150 T.D. 6093'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface				8 5/8"	1541	0'
Production				4 1/2"	3363'	2000'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pump 2 Skts. hulls & 20 Skts. cement to 2800'
Pressured to 1500 lbs. Mud to 1590'
Pump 50 Skts. cement 1590' to 1490', mud 1490' to 900'
Pump 50 Skts. cement 900' to 800', mud 800' to 40'
Bridge & 10 Skts. 40' to 3', cut off 8 5/8", 3' below ground level and cap

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497
Address Box F, Sublette, Ks. 67877

STATE OF KANSAS COUNTY OF HASKELL, ss.

I, Edgar J. Eyes (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

SONDRA L. EVES
NOTARY PUBLIC - STATE OF KANSAS
My Appt. Exp. 12-6-92

(Signature) Edgar J. Eyes

(Address) Box F, Sublette, Ks. 67877

SUBSCRIBED AND SWORN TO before me this 17 day of May, 1990

Sondra L. Eves
Notary Public

My Commission expires: 12-6-92

RECEIVED
STATE CORPORATION COMMISSION
13 1990
5-31-1990
CONSERVATION DIVISION
Wichita, Kansas