

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-119-30070-0000

API NUMBER _____
 LEASE NAME Bessmer
 WELL NUMBER #1
1320 Ft. from S Section Line
1980 Ft. from E Section Line
 SEC. 1 TWP. 33 RGE. 29 (E) or (W)
 COUNTY Meade
 Date Well Completed 12-16-65
 Plugging Commenced 9-25-87
 Plugging Completed 10-1-87

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR George R. Shaw, (Edwin Bradley)
 ADDRESS 1001 Union Center, Wichita, Ks. 67202
 PHONE# (316-267-0382) OPERATORS LICENSE NO. 5062

Character of Well oil and gas
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? One (1)

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 5663'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS			CASING RECORD			
Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	1412'	None
				4-1/2"	5641'	2,551.94"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet, each set. Dumped sand to 5,510' and 4 sacks cement. Shot casing at 4500', 3500', 3150', 3000', 2800' and 2500'. Pulled 79 joints of 4-1/2" casing. Halliburton squeezed well with 3 sacks hulls, 3 sacks gel, and 150 sacks Econolite cement. Maximum pressure was 150 psi and shutin 50 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. RECEIVED
Box 698 STATE CORPORATION COMMISSION
 Address Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss. OCT 12 1987
10-12-1987

James W. Rockhold (Employee of Operator CONSERVATION DIVISION) of
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
 statements, and matters herein contained and the log of the above-described well as filed that
 the same are true and correct, so help me God.

(Signature) James W. Rockhold
 (Address) James W. Rockhold
Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 6th day of October, 1987

STATE NOTARY PUBLIC
 IONA M. LEATHERMAN
 Barton County, Kansas
 My Appt. Exp. 9-16-87

Iona M. Leatherman
 Notary Public

My Commission Expires _____

LEASE: BESSMER #1
OWNER: EDWIN G. BRADLEY
CONT: EARL F. WAKEFIELD
COMM: 7-9-65
COMP: 7-25-65

LOCATION: C W/2 SE/4
SECTION 1-33S-29W
MEADE COUNTY, KANSAS
CASING: 8 5/8" Set @ 1412'
4 1/2" Set @ 5641'

Clay & Sand	691
Red Bed	926
Glorietta Sand	1030
Shale & Red Bed	1412
Shale	1805
Shale & Lime	2448
Lime & Shale	2790
Lime	3219
Lime, Shale, Chalk	3510
Shale & Chalk	3563
Lime	3740
Shale	3860
Shale & Lime	4089
Lime & Shale	4666
Lime	5660
R.T.D.	5660

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, FRED S. BARKER, DO HEREBY CERTIFY THAT THE ABOVE IS A TRUE AND
CORRECT COPY OF THE DRILLER'S LOG ON THE BESSMER #1, LOCATED IN THE
C W/2 SE/4 of SECTION 1-33S-29W, MEADE COUNTY, KANSAS.

RECEIVED
STATE CORPORATION COMMISSION
JUL 24 1965
CONSERVATION DIVISION
Wichita, Kansas

EARL F. WAKEFIELD
BY Fred S. Barker

SUBSCRIBED AND SWORN TO BEFORE ME THIS 3rd DAY OF AUGUST, 1965.

MY COMMISSION EXPIRES:
January 14, 1966

Frances O. Erhard
Frances O. Erhard NOTARY PUBLIC