

15-119-00110-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Meade County. Sec. 7 Twp. 33S Rge. 28 (W)

Location as "NE/CNW/SW" or footage from lines 660' N of the S and 660' E of

Lease Owner Shamrock Oil & Gas Corp. the West

Lease Name Jo Fletcher Well No. #1

Office Address Mr. Ace Baldwin, Dumas, Texas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed Yes 19

Application for plugging approved Yes 19

Plugging commenced 4-13 19 59

Plugging completed 4-17 19 59

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Merle A. Rives

Producing formation Depth to top Bottom Total Depth of Well 5717' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				9 5/8"		
				5 1/2"		5,088'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Measured into T.D. 5717'.

Plugging started 4-13-59. Finished 4-17-59.

Cleaned out cellar, welded on collar. Worked pipe. Sanded to 5565', and dumped 5 sacks cement. Worked and shot pipe. Shot 5 1/2" casing at 5,088'. Pulled pipe out of hole and plugged well as follows:

Mudded to 600'. Set rock bridge and dumped 20 sacks cement. Mudded to 300'. Set rock bridge and dumped 20 sacks cement. Filled hole with mud, set rock bridge and capped well with 10 sacks cement. Well completed.

APR 28 1959  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J.O. Forbes d/o/a Forbes Casing Pulling Co.

Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

J.O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes

Box 221, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 27th day of April, 1959

Betty S. Edman

Notary Public.

My commission expires November 8, 1960.

PLUGGING  
FILE SEC. 7 T. 33 S. R. 28 W  
BOOK PAGE 27 LINE 28

15-119-00110-0000

JOE S. FLETCHER NO. 1  
(Section 7, Township 33 South, Range 28 West)  
Meade County, Kansas

0'	-	145'	Red Bed
145'	-	1,403'	Red bed & sand
1,403'	-	1,552'	Shale & shells
1,552'	-	1,560'	Shale
1,560'	-	1,640'	Red bed
1,640'	-	1,995'	Shale & red bed
1,995'	-	2,187'	Shale & shells
2,187'	-	2,310'	Shale & lime
2,310'	-	2,660'	Lime
2,660'	-	2,803'	Sandy lime
2,803'	-	3,214'	Lime
3,214'	-	3,611'	Lime & shale
3,611'	-	3,780'	Lime
3,780'	-	4,007'	Shale & lime
4,007'	-	4,150'	Lime
4,150'	-	4,378'	Lime & shale
4,378'	-	5,585'	Lime
5,585'	-	5,635'	Sand
5,635'	-	5,640'	Shale
5,640'	-	5,652'	Lime
5,652'	-	5,654'	Shale
5,654'	-	5,658'	Lime
5,658'	-	5,660'	Shale
5,660'	-	5,716'	Lime

RECEIVED  
STATE CORPORATION COMMISSION  
APR 6 1959  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 7 T 33 R 28 W  
BOOK PAGE 27 LINE 28