

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Meade County, Sec. 9 Twp 33S Rge. (E) 28 (W)

Location as "NE/CNW/SW" or footage from lines SW NW NW
Lease Owner Surray Mid-Continent Oil Company
Lease Name J. M. Riddle Well No. 1
Office Address 321 West Douglas - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 4 19 60
Application for plugging filed July 6 19 60
Application for plugging approved July 7 19 60
Plugging commenced July 18 19 60
Plugging completed July 22 19 60
Reason for abandonment of well or producing formation Dry

NORTH

Section Plat grid with 'x' in the top-left cell.

Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production --- 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. LaKamp
Producing formation --- Depth to top --- Bottom --- Total Depth of Well 5735 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Rows include Morrow (Dry) and Mississippi (Water).

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from --- feet to --- feet for each plug set.

Filled hole with mud to 5500'. 10 sack cement plug 5500' to 5340'. Twenty sack cement plug 600' to 536'. Mud from 536' to 32'. Ten sack cement plug from 32' to surface.

RECEIVED
STATE CORPORATION COMMISSION

JUL 26 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Toland and Reeves
Address Oklahoma City

STATE OF Kansas, COUNTY OF Sedgwick ss.
Nash A. Gough (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
321 West Douglas - Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 25 day of July, 19 60

My commission expires July 13, 1963 [Signature] Notary Public.

15-119-10202-0000

Sunray Mid-Continent
Tulsa, Oklahoma

Tulsa, Oklahoma
March 7, 1960

CONTRACTOR: Stickle Drilling Company
DRILLING COMMENCED: February 16, 1960
DRILLING COMPLETED: March 5, 1960

Riddle #1 SW NW NW
9-33S-28W, Meade
County, Kansas.

DRILLERS LOG

Depth Figures Indicate Base of Formation:

Surface	0
Sand & Clay	140
Red Bed	525
Red Bed & Shale & Shells	1345
Shale & Anhydrite Stringers	1544
Shale & Shells	2360
Shale & Lime	2520
Lime & Shale	4668
Lime	5518
Lime & Sand	5558
Lime	5608
Lime & Shale	5735 TD

I, Fred E. Stickle, hereby certify the above to be a true and complete
Drillers Log of Sunray Mid-Continent Oil Company's Riddle #1 SW NW NW
Section 9-33S-28W, Meade County, Kansas.

Fred E. Stickle
Fred E. Stickle

Francis L. Gager
Notary Public

January 8, 1964
My Commission Expires

RECEIVED
STATE CORPORATION COMMISSION

JUL 26 1960

CONSERVATION DIVISION
Wichita, Kansas