

11-30

To: 1 020193  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-129-20,440-000  
NE SW SW, SEC. 3, T 31 S, R 42 WAE

1250 feet from S section line  
4030 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Wilder Well # 1

Operator: TXO Production Corporation  
Name & Address: 1660 Lincoln Street, Suite 1800  
Denver, CO 80264

County Morton 104.36

Well Total Depth 3211 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 605

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SHD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 10 a.m. Day: 28 Month: 11 Year: 1988

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 4 1/2" at 3211' PRTD 3005'-CTRP Perfs at 2901-05, 2838-58' TOC 2700'

1st plug pump 1 sx hulls and 25 sx cement to bottom

2nd plug pump 50 sx cement r 1450'

3rd plug pump 30 sx cement at 825'

4th plug pump 50 sx cement at 630', 5th plug pump cement at 40-0'

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 3 p.m. Day: 30 Month: 11 Year: 1988

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 25 sx cement,

2nd plug ran 50 sx cement at 1450'-1200',

3rd plug ran 30 sx cement at 825-660',

4th plug ran 50 sx cement at 630-430',

5th plug ran 10 sx cement at 40-0'.

Remarks: Used common cement by Sargent's. Recovered 2205' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED  
DATE 12-12-88  
INV. NO. 23311

Signed *John P. Barlow* (TECHNICIAN)