

1 020175

15-12A-10165-0000 317

R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 9/27/55

C NW/4, SEC. 4, T 31 S, R 42 W/EX

3960 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6981

Lease Name Herron Well # 1

Operator: Gas Marketing

County Morton 173.39

Name & Address

Well Total Depth 5335 feet

P.O. Box 737

Conductor Pipe: Size feet

Salina, KS 67402

Surface Casing: Size 10 3/4 feet 1367

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor: Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 8:30 a.m. Day: 25 Month: 8 Year: 19 88

Plugging proposal received from Dallas Fulls

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 7" at 5335' PBTD 3530' Perfs at 3372-80'

1st plug sand back to 3300' and dump 7 sx cement on top of sand through bailer,

2nd plug pump 70 sx cement at 1367'

3rd plug pump 50 sx cement at 650'

4th plug pump 15 sx cement at 15'

RECEIVED  
STATE CORPORATION COMMISSION

AUG 31 1988

Plugging Proposal Received by Dan Goodrow

CONSERVATION DIVISION  
Wichita, Kansas (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 5 p.m. Day: 25 Month: 8 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 3300' and dumped 7' sx cement on top of sand,

2nd plug shot off at 1900', pulled to 1500', pumped 10 sx gel,

pulled to 1375' and ran 70 sx cement,

3rd plug pulled 7" to 1100', ran 15 sx gel, pulled to 700', ran 10 sx gel and 50 sx

cement,

4th plug pulled 7" to 65' and cemented to surface.

Remarks: Used 60/40 Pozmix 3% gel by Allied. Recovered 1900' of 7" casing.

(if additional description is necessary, use BACK of this form.)

INVOICED  
I hereby certify that I have observed this plugging.

DATE 9-7-88

Signed Glenn R. Barber (TECHNICIAN)

INV. NO. 22140