

1060322

R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-175-20,496-0000

C NW, SEC. 31, T 31 S, R 31 W/E

3960 feet from N SE Corner of section line

3960 feet from W SE Corner of section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5219

Lease Name Felan Well # 1

Operator: Kimbark Oil & Gas Company

County Seward

Name & Address 1580 Lincoln St., Suite 700

Well Total Depth 2790 90.68 feet

Denver, CO 80203

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 690

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Arapahoe Well Service License Number 5476

Address 535 North Oliver, Wichita, KS 67208

Company to plug at: Hour: 1:00 pm Day: 30 Month: August Year: 19 84

Plugging proposal received from Raymond Eaves

(company name) Arapahoe (phone)

were: 4 1/2" set at 2790' Perfs at 2658-64'

1st plug pump 2 sx hulls and 25 sx cement to bottom

2nd plug at 1680' with 35 sx cement

3rd plug at 740' with 40 sx cement solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

Plugging Proposal Received by Paul A. Luthin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 3:00 pm Day: 30 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 2790' Perfs at 2658-64'

1st plug pumped 2 sx hulls and 25 sx cement to bottom, 2nd plug at 1680' with 35 sx

cement, 3rd plug at 740' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement.

Remarks: Used Common sacked cement by Midwest casing

If additional information is necessary, use BACK of this form.)

INVOICED

DATE 9-14-84

INV. NO. 3674

RECEIVED  
SEP 14 1984  
9-4-84  
CONSERVATION DIVISION  
Wichita, Kansas

Signed Paul A. Luthin (TECHNICIAN)